

Scope of the Works

The scope of the work is the removal of an approximately 100mm band of internal plaster to the Tower West Wall (to include the west wall of the main entrance vestibule), located at the base of the all, at floor level:

- see Matthew Beesley's "Tower West Wall Moisture Accumulation Report";
- See the photos attached;
- See the marked-up floor plan attached.

It is important to remember that the measure currently being proposed is a preliminary measure – following his planned future monitoring of the moisture levels in this location at 12- and 24- months, he may suggest that further measures would be appropriate in due course (though this would all need to be confirmed).

The proposal should be read in conjunction with the current work to remove the external concrete hardstanding located at the base of the Tower (West Elevation), and the reinstatement of the ground with turf.
Faculty 1426

How Matthew Beesley Proposed The Work Be Undertaken?

Matthew proposes that a line is scribed on the wall at the correct height (care will need to be taken to avoid damaging or destabilising the existing surface-mounted electric cables and clips. The precise method to cut the line is to be confirmed on-site but is likely to require a multi-blade saw/tool. The face of the stonework behind the plaster is to be left exposed. Some minor re-clipping of the cables is thought likely to be needed.